

Improving Progress Monitoring by Fusing Point Clouds, Semantic Data and Computer Vision

Alex Braun^{a,c}, Sebastian Tuttas^{b,c}, André Borrmann^{a,c}, Uwe Stilla^{b,c}

^a*Chair of Computational Modeling and Simulation, Technical University of Munich,
Germany*

^b*Chair of Photogrammetry and Remote Sensing, Technical University of Munich,
Germany*

^c*Leonhard Obermeyer Center, TUM Center of Digital Methods for the Built Environment*

Abstract

Automated construction-progress monitoring enables the required transparency for improved process control, and is thus being increasingly adopted by the construction industry. Many recent approaches use Scan-to/vs-BIM methods for capturing the as-built status of large construction sites. However, they often lack accuracy or are incomplete due to occluded elements and reconstruction inaccuracies. To overcome these limitations and exploit the rich project knowledge from the design phase, the authors propose taking advantage of the extensive geometric-semantic information provided by Building Information Models. In particular, valuable knowledge on the construction processes is inferred from BIM objects and their precedence relationships. SfM methods enable 3D building elements to be located and projected into the picture's 2D coordinate system. On this basis, the paper presents a machine-learning-based object-detection approach that supports progress monitoring by verifying element categories compared to the expected data from the digital model. The results show that, depending on the type of construction and the type of occlusions, the detection of built elements can rise by up

to 50% compared to an SfM-based, purely geometric as-planned vs. as-built comparison.

Keywords: Construction progress monitoring, BIM, point clouds, semantic and temporal knowledge, deep learning

1. Introduction

1.1. Automated progress monitoring

Construction progress monitoring is currently still performed mostly manually, in a laborious and error-prone non-automated process. To prove that all works have been completed as agreed contractually, all completed tasks must be documented and monitored. Complete and detailed monitoring techniques are required for large construction sites where the entire construction area and the number of subcontractors become too large for manual tracking to be efficient. Detecting possible deviations from the schedule provides a benchmark for the performance of the construction site. Regulatory matters add to the requirement of keeping track of the current status on the site. The ongoing establishment of building information modeling (BIM) technologies in the planning of construction projects facilitate the application of digital methods also in the execution phase. In an ideal implementation of BIM, all relevant information on materials, construction methods, and even the process schedule are interlinked. On this basis, it is possible to estimate project costs and project duration more precisely than with conventional methods [1].

On top of the digitized construction design process, recent advancements for capturing the as-built geometry by laser scanning [2] or photogrammetry [3] allow using the resulting point cloud data to be compared against the as-planned model. Photogrammetry, in particular, has gained more attention with the broader availability of Unmanned Aerial Vehicles (UAVs), making this method more flexible in terms of camera positions [4]. The main idea is not to use laser scanners but conventional camera equipment on construction

26 sites to capture the current construction state ("as-built"). Since the ac-
27 quisition from different perspectives is significantly faster than laser scanners,
28 the building can be captured in a comprehensive manner with comparatively
29 low effort. As soon as a sufficient number of images from different points of
30 view are available, a 3D point cloud can be produced using Structure from
31 Motion (SfM) methods [5]. Finally, the point cloud, representing one par-
32 ticular observation time-point, can be compared against the geometry of the
33 Building Information Model.

34 *1.2. Problem statement*

35 Currently, the detection of built elements using SfM methods and other
36 point-cloud-based approaches faces several challenges:

37 *1.2.1. As-planned modeling vs. as-built construction*

38 As introduced in Braun et al. [6], the as-planned model is represented
39 by a 4D building information model (see Figure 1 a)). All 4D construction
40 processes are linked to their associated elements, allowing for statements re-
41 garding the expected construction state at any given observation time. As
42 the relevant model and point cloud are co-registered, an initial detection al-
43 gorithm can compare the model's geometry with the 3D information from
44 the point cloud. During the construction phase, the actual as-built process
45 can deviate from the original as-planned process. To clarify this deviation,
46 Figure 1 depicts the digital model from one of the test sites, a corresponding
47 UAV-aerial image, and the generated point cloud (a), c) and d)). Ac-
48 cordingly, the as-planned 4D model does not represent the real construction
49 sequencing. This problem is also described in Huhnt et al. [7], Tulke [8].




Figure 1: Process modeling problems depicted by a) as-planned modeling, b) as-built modeling, c) as-built image, d) as-built point cloud on sample construction site.

50 In comparison, Figure 1 b) shows the correct corresponding as-planned
51 model for the given timestamp, with all subsequent elements being removed
52 from the as-scheduled model.

53 *1.2.2. Reconstruction*

54 The monitoring of construction sites by applying photogrammetric meth-
55 ods has become common practice. Currently, several companies (for exam-
56 ple, Pix4D or DroneDeploy) provide commercial solutions for end users that
57 permit the generation of 3D meshes and point clouds from UAV or other
58 image-based site observations. All these methods provide proper solutions
59 for finished construction sites or visible elements of interest.

60 However, UAV-based monitoring of construction sites exhibits several
61 problems. On the one hand, photogrammetric methods are sensitive to low-
62 structured surfaces like monochrome painted walls, or windows. Because of
63 the used method, each element needs to be visible from multiple (at least
64 two) different points of view. Thus, elements inside of a building cannot be
65 reconstructed as they are not visible from a UAV flying outside of the build-
66 ing. Monitoring inside of a building is currently still the subject of much
67 research [9] and not available via an automated method, as localization in
68 such mutable areas like construction sites is hard to tackle. These problems
69 lead to holes or misaligned points in the final point cloud, which hinders the
70 accurate and precise detection of building elements. On the other hand, laser
71 scanning requires many acquisition points and takes significantly more time
72 and manual effort in acquisition.

73 *1.2.3. Occlusions*

74 Finally, both techniques are challenged by occlusions for regions that
75 are not visible during construction. The as-built 3D point cloud with n
76 points holds all respective coordinates but also color information based on
77 the feature's pixel color value in the initial image. The value n depends on
78 many factors such as

- 79 • lighting conditions
- 80 • feature detection from different points of view
- 81 • surface textures
- 82 • amount and resolution of the images taken

83 A point cloud from one timestamp on one of our test construction sites
84 can be seen in Figure 1 d). Besides scaffolding and formwork, various holes
85 are visible in the point cloud that exist due to insufficient image quality for
86 reconstruction or occlusions. The depicted point cloud matches the expected
87 quality for an as-built acquisition and is incomplete due to changing visibility
88 conditions from working equipment and similar items. However, it is not
89 sufficient for reliable results in a purely geometric as-planned vs. as-built
90 comparison as significant parts of the actual building are occluded. As seen
91 in figure 2, another problem lies in elements that are occluded by temporary
92 construction elements. In particular, scaffolding and formwork occlude the
93 direct view on walls or slabs, making it harder for algorithms to detect the
94 current state of construction progress.



Figure 2: Occluded construction elements in generated point cloud caused by scaffolding, formworks, existing elements and missing information during the reconstruction process

95 Currently available methods do not take these problems into account and
96 make only limited use of BIM-related information such as type of construction
97 and the general structure of a building.

98 1.3. Contributions

99 In this paper, the authors propose a number of inter-related methods
100 to tackle the aforementioned problems. Specifically, this paper presents the
101 following contributions:

- 102 • Known technological dependencies of construction sequences are used
103 to enrich the model by precedence relationships, by applying formal
104 graph theory. This allows the inference of the existence of elements, if
105 they have not been directly detected.
- 106 • A method is presented that makes use of the knowledge of construction

107 methods and 4D data to adjust the detection thresholds (as-planned vs.
108 as-built deviations allowed) according to their expected construction
109 stage. This permits the detection of elements that are currently under
110 construction and are, for example, covered by formwork.

- 111 • We introduce a method based on visibility analysis to identify elements
112 that are detectable from the identified camera positions. Deep learning
113 on projected element positions in the 2D plane of the gathered images
114 for the initial SfM process allows the detection rates of built elements
115 to be further enhanced.

116 The combined application of these methods helps to significantly improve
117 the accuracy of construction progress monitoring, as documented by the case
118 studies presented in this paper.

119 The details of the individual methods are described in Section 3.

120 **2. Related Work**

121 *2.1. Scan vs. BIM*

122 Progress monitoring has become a heavily researched topic in recent years.
123 Omar and Nehdi [10] provide an overview of these developments and compare
124 the individual approaches:

125 The as-built status of a construction site is usually captured by laser
126 scanners or cameras using SfM methods. Laser scanning has the advantage
127 that 3D point measuring is fast and very accurate (within the range of mil-
128 limeters). However, the equipment is heavy and requires trained personnel.
129 Additionally, the setup at the point of observation is time-consuming and,

130 depending on the size of the construction site, many observation points are re-
131 quired to scan the whole construction site. Photogrammetric approaches pro-
132 duce less accurate point clouds in comparison to laser scanning and require
133 significant computing power for the reconstruction. However, this method is
134 more flexible and easier in its application, as camera equipment is standard,
135 low-cost, and widely used on UAVs. Other devices, such as Microsoft Kinect,
136 combine multiple sensors and can also be used for progress monitoring [11].

137 The registration of the acquired point cloud and corresponding as-planned
138 geometry is either performed manually or semi-automatically, e.g. by point-
139 to-point matching through Iterative Closest Point (ICP) algorithms. Here,
140 the algorithm minimizes the distance between the points of the laser scan
141 and the BIM geometry [12].

142 Currently, three methods are deemed to be established in the comparison
143 with the as-planned status:

- 144 1. comparison of points from the as-planned geometry with as-built point
145 clouds. These methods compare point clouds that are acquired by laser
146 scanners [13, 14] or SfM methods and derived point clouds from as-
147 planned surfaces [15]. Point proximity metrics mainly do this following
148 a data-alignment process.
- 149 2. Feature detection in the acquired images from the as-built state. Us-
150 ing feature detection algorithms to assess the progress of as-planned
151 elements (as the construction site evolves in time) by comparing mea-
152 surements with dynamic thresholds learned through a Support Vector
153 Machine (SVM) classifier, construction elements are directly identified
154 from the acquired images [16].

155 3. Matching the as-planned geometry surfaces directly with the as-built
156 points. Here, relevant points from the point cloud are directly matched
157 onto triangulated surfaces of the as-planned model after using octree-
158 based checks for occupied regions [17].

159 The first approaches involving object detection in laser-scanned point
160 clouds were published by Bosché and Haas [2]. Turkan et al. [14] extend this
161 system and uses it for progress estimation. Kim et al. [18] detect specific
162 component types using a supervised classification based on Lalonde features
163 derived from the as-built point cloud. An object is regarded as detected if the
164 type matches the type present in the model. As above, this method requires
165 that the model is sampled into a point representation. Zhang and Arditi
166 [19] introduce a measure for deciding four cases (object not in place, point
167 cloud represents a full object or a partially completed object or a different
168 object) based on the relationship of points within the boundaries of the object
169 and the boundaries of the shrunk objects. However, the authors test their
170 approach in a very simplified artificial environment, which is significantly less
171 challenging than the processing of data acquired on real construction sites. In
172 Mahami et al. [20], SfM and Multi-View Stereo (MVS) algorithms are coupled
173 with coded targets to improve the photogrammetric process itself. Ibrahim
174 et al. [21] use a single camera approach and compare images taken during
175 a specified period, and rasterize them. Individual elements are identified
176 for each use case. Most publications focus on identifying one particular
177 type of element like, for example, columns or walls. Indoor monitoring has
178 been researched by several groups. Asadi et al. [22] propose a new method
179 to localize and align the camera position and building model in a real-time

180 scenario. Kropp et al. [23] tried to detect in-door construction elements based
181 on similarities. Turkan et al. [24] present an approach for detecting elements
182 under construction that uses threshold extensions for those elements. Han
183 and Golparvar-Fard [25] published another attempt to solve the problem of
184 elements under construction. The focus lies on visibility issues, e.g., assuming
185 that an anchor bolt for a column must be present, despite being invisible,
186 as the column on top of it requires the anchor bolt for structural reasons.
187 Further research has been conducted in regard to multi-layered elements and
188 the introduction of construction sequencing [26].

189 Another critical aspect of the as-planned vs. as-built comparison is de-
190 pendencies. Technological dependencies determine which element is depend-
191 ing on another element, meaning that it cannot be built after the first ele-
192 ment is finished. Precedence relationships [27] can define these dependencies.
193 Szczesny et al. [28] discuss a storage solution for these dependencies. The ap-
194 proach with regard to progress monitoring is presented in Braun et al. [29].
195 Hamledari et al. [30] introduce an IFC-based schedule updating workflow
196 that relies on detected construction elements.

197 In their outlook, Turkan et al. [24] state that further improvements to
198 their work should include color analysis or even image-based methods. Thus,
199 the authors propose incorporating these techniques, as well as the use of se-
200 mantic data like construction methods, model analysis using technological
201 dependencies, and image-based deep learning, to further enhance the detec-
202 tion of elements in an as-planned vs. as-built comparison.

203 *2.2. Computer vision and deep learning*

204 Rising computational power has enabled significant advances in machine
205 learning in recent years. Deep learning [31] and especially Convolutional Neu-
206 ronal Networks (CNN) provide solutions for training computers to learn pat-
207 terns and apply them to previously unseen data. In this context, computer
208 vision is a heavily researched topic that has received even more attention
209 through recent advances driven by, for example, the needs of autonomous
210 vehicles. Image analysis in the construction sector, on the other hand, is
211 a rather new topic. Up to now, the main focus has been on defect detec-
212 tion (for example, cracks) in construction images [32]. Crack detection for
213 asphalt roads has also been the subject of research [33]. Since one of the
214 critical aspects of machine learning is the collection of large datasets, cur-
215 rent approaches focus on data gathering. In the scope of automated progress
216 monitoring, Han and Golparvar-Fard [34] published an approach for labeling
217 image datasets based on the commercial service Amazon Turk. Braun and
218 Borrmann [35] introduce a method for automated image labeling by fusing
219 semantic and photogrammetric data.

220 Regarding the application of deep learning for construction progress track-
221 ing, Chi and Caldas [36] used initial versions of neural networks to detect
222 construction machinery on images, and Kim et al. [15] used ML-based tech-
223 niques for construction progress monitoring. They analyzed images by fil-
224 tering them to remove noise and uninteresting elements, so as to focus the
225 comparison on relevant construction processes. Hamledari et al. [37] applied
226 CV approaches to indoor appliances like electrical outlets and insulation.

227 These approaches are currently mostly independent from the actual build-

228 ing model, as orientation and scale with respect to the digital twin are ne-
229 glected or assumed to be given for the application of CV methods. The
230 application of these methods, in combination with SfM-based orientation
231 data, has not been the subject of research to date.

232 **3. Concept**

233 *3.1. Objective*

234 The main goal of this research is to improve the results of element detec-
235 tion from a point-cloud-based as-planned vs. as-built comparison by using
236 additional information provided through the Structure-from-Motion process
237 (images and camera positions), as well as the as-designed building informa-
238 tion model (semantic data, geometric representation of elements, and position
239 and dependencies of elements). The following concept presents the proposed
240 solutions to tackle the mentioned challenges with several approaches, such
241 as incorporating additional information on construction methods into the
242 comparison algorithms.

243 *3.2. Point of departure*

244 The concept builds upon the body of knowledge of the research com-
245 munity as well as the previous research conducted by the authors. Thus,
246 several steps in the process of automated progress monitoring are assumed
247 to be given. Firstly, image acquisition for the generation of point clouds and
248 camera position estimation is required. The authors provided several studies
249 on image acquisition and proposed a UAV-based method as it is more flex-
250 ible in comparison to fixed cameras [38]. Secondly, the point cloud and the

251 as-designed building information model must be aligned to one another (also
252 known as registration). According to the well-documented state of the art,
253 this is either performed via geodetic reference points that align the as-planned
254 digital model with the point cloud on the measured geodetic position, via au-
255 tomated ICP methods (as mentioned earlier), or manually via point-to-point
256 picking. The authors provide a detailed description of these approaches in [6]
257 and [35]. In this paper, we significantly extend the state-of-the-art approach
258 by using computer vision (CV) methods.

259 *3.3. Concept overview*

260 The concept presented in this paper relies on the exploitation of as-design
261 building information models to improve the progress-detection process. We
262 assume them to be available as IFC instance models. These models provide
263 a geometric representation of all relevant building components, as well as
264 the related semantic information (such as component type, material or the
265 attribute "load-bearing") as well as 4D process data. The general idea is
266 to enhance the purely geometric as-planned vs. as-built comparison from
267 point-cloud to geometry level, with additional layers of information. Fig. 3
268 depicts the conceived processing chain. The highlighted process components
269 provide new elements that are introduced in this paper. After defining the
270 different sets of building elements required for the process in Sec. 3.4, these
271 new elements are explained in detail in dedicated subsections.

272 The creation of the precedence relationship graph is discussed in Sec. 3.5.
273 The following sections focus on schedule analysis (Sec. 3.6), and color detec-
274 tion (Sec. 3.7). The latter process step helps to identify whether an element
275 is present or occluded by other structures. Finally, we introduce a method

276 that projects the 3D as-designed geometry provided by the building informa-
277 tion model into the 2D plane, so as to apply image analysis techniques for
278 element detection. Sec. 3.8 describes the projection process. Subsequently,
279 Sec. 3.9 discusses the application of computer vision methods to detect the
280 type of the element that is visible in the projected region of interest.

281 The combination of these individual processing steps results in a signifi-
282 cant improvement in the accuracy of the overall automated progress detection
283 method, as demonstrated through the case studies presented in Section 4.6.

284 *3.4. Sets of elements and detection status*

285 In the context of the research presented, the following sets of construction
286 elements are defined in regard to as-built vs. as-planned comparison:

- 287 • E represents all elements of the current building
- 288 • $E_P(t)$ defines the amount of elements that should be present at the
289 time t of observation according to the as-planned schedule
- 290 • $E_{GT}(t)$ defines the ground truth as all elements that are built at obser-
291 vation t
- 292 • $E_D(t)$ defines all elements that were detected during an observation at
293 timestamp t
- 294 • $E_{ND}(t)$ defines all elements that were not detected during an observa-
295 tion at timestamp t
- 296 • $E_V(t)$ defines all elements that are visible from the corresponding points
297 of view during observation at timestamp t




Figure 3: Concept for the enhancement of element detection. The highlighted process steps are introduced in this paper.

298 t defines the observation timestamp, at which the construction site has
299 been monitored.

The following definitions hold true for all given sets at any timestamp t :

$$E = E_D(t) \cup E_{ND}(t) \quad (1)$$

$$E_D(t) \leq E_V(t) \leq E_{GT}(t) \leq E \quad (2)$$

According to these definitions, the set of *TruePositives* is defined as

$$E_{TP}(t) = E_D(t) \cap E_{GT}(t) \quad (3)$$

while *FalsePositives* are the counterpart:

$$E_{FP}(t) = E_D(t) \setminus E_{GT}(t) \quad (4)$$

The goal of this research is to verify as many existing construction elements as possible, so as to minimize the differences between these sets while keeping $E_{FP}(t)$ minimized. Mathematically speaking:

$$E_D(t) \longrightarrow E_{GT}(t) \quad (5)$$

300 It is not possible to define a relation between the planned elements $E_P(t)$
301 and the ground truth $E_{GT}(t)$ as the progress of the construction site depends
302 on many external factors that cannot be formalized with the given data.
303 The set of $E_P(t)$ can contain more elements than $E_{GT}(t)$ in the event of a
304 delay on the construction site but also fewer elements in the event of faster
305 construction times.

306 In addition to the mentioned sets, every construction element is classified
307 individually for each of the following states: built (Ground Truth), detected,
308 planned, encased in formwork, under construction.

309 These definitions are used in the described concepts.

310 *3.5. Process sequencing and precedence relationships*

311 As-built monitoring with SfM methods or laser scanning always captures
312 one particular timestamp.

313 For automated handling of dependencies, a precedence relationship graph
314 (PRG) is introduced [29]. The PRG formalizes technological dependencies
315 between construction elements and is defined as a directed, acyclic graph
316 (DAG) with each node representing one construction element [39]. Techno-
317 logical dependencies for load-bearing structures between two elements can
318 be automatically detected when they have a particular spatial constellation
319 that, in combination with the construction method applied, unambiguously
320 defines their sequential order. For example, when conventional in-situ con-
321 creting methods are applied, a slab on top of a column can only be built
322 after the column is finished. To generate this graph, the semantic as well
323 as the geometric data from the digital model is used in combination with a
324 knowledge base representing the construction methods. The geometric data
325 is used to identify elements that are touching each other, and for sequencing
326 them in their respective vertical order. Additionally, the semantic data is
327 used to determine the construction method for an individual element, and to
328 filter load-bearing elements. The generation of the initial precedence graph
329 is performed as depicted in Algorithm 1. This method relies on a spatial
330 query language, as introduced in Daum and Borrmann [40].

Algorithm 1 Pseudo code for the generation of an initial Precedence Relationship Graph

```
1: procedure GENERATEPRECEDENCERELATIONSHIPGRAPH
2:    $E \leftarrow$  set of all construction elements
3:   for all  $E(\text{LoadBearing})$  do
4:     for all  $ET$  do
5:       if Above( $E(\text{LoadBearing}), ET$ ) then
         AddDirectedEdge( $E(\text{LoadBearing}), ET$ );
```

331 The initial precedence graph is completed manually in order to take
332 project-specific boundary conditions and non-spatial precedence relation-
333 ships into account.

334 The PRG is used to identify objects that are possibly under construction
335 at the time of observation.

336 Using the introduced PRG, it is possible to identify elements that might
337 be under construction and thus are considered for further investigation. The
338 basic flowchart depicted in Figure 3 shows the implemented workflow for
339 enhanced detection.

340 Based on the construction type and the erection method, different steps
341 follow. As detailed above, walls and other vertically erected elements are
342 considered for an extended threshold in order to identify possible formwork.
343 Additionally, color matching helps to differentiate the material properties.

344 Moreover, the PRG allows for assumptions with regard to elements that
345 are invisible due to occlusions, and thus not directly detectable. For example,
346 load-bearing columns underneath a detected slab are expected to be built
347 even if it is not possible to verify them via the point cloud.

348 *3.6. Identified tasks during construction*

349 Several tasks are required to construct in-situ concrete elements or similar
350 elements. In concrete construction, formwork for in-situ concrete is the most
351 common construction method. Several different methods are depicted in
352 Figure 1 b) and d). All possible elements under construction are considered
353 in order to detect formwork. In general, elements are counted as detected as
354 soon as a certain amount of points per area [Pts/m^2] with a distance of less
355 than 2 cm are matched on the surface of the element [41]. If the expected
356 elements are not detected, the threshold for the maximum distance can be
357 adjusted to take into account the fact that the formwork with a thickness of
358 around 0.20m might be currently in place. If this iteration brings positive
359 results, the element can be marked as "under construction".

360 *3.7. Color detection*

361 In general, formwork for walls and columns consists of a wooden, smooth
362 plate on the concrete side, and a steel structure for stability on the backside.
363 This steel structure is often painted red, yellow or orange, and is distinct from
364 the gray concrete. Formwork for slabs usually consists of elevated wooden
365 plates that have the same color range as the steel structure mentioned. This
366 color difference can be measured and may help to further improve the de-
367 tection quality of formwork. The HSV (Hue-Saturation-Value) color space
368 provided useful data for the color detection [42]. In contrast to the RGB
369 color space, the HSV color space can describe color as perceived by humans
370 but also saturation and brightness (value). Each value has a range from 0 to
371 1.

372 Comparing the color distribution of identified subsections of the point
373 cloud can consequently help to achieve further verification of the existence
374 of an element. The material color, as well as the type of construction, is
375 retrieved from the building information model in order to gather color infor-
376 mation. After identifying a gray color distribution for an expected concrete
377 element, this data further confirms the existence of said element. In compar-
378 ison, a mainly red or orange color distribution leads to the assumption that
379 a formwork element is present, if the initial element has not been verified but
380 is meant to be constructed with in-situ concrete.

381 *3.8. Visibility analysis and projection of elements*

382 Photogrammetry is based on estimating the position of all cameras that
383 are used for the point cloud generation. Since the digital model of the con-
384 struction sites is aligned to the point cloud during the comparison process,
385 it is possible to project the 3D geometry of all elements into the respective
386 2D plane of a corresponding image [35]. Knowing the expected position of
387 an element in image space enables highly accurate object-detection to be
388 performed, using CV approaches.

389 More specifically, it is possible to perform a visibility detection by using
390 the camera parameters to compute the projection of the model elements onto
391 image space and of the process information, to define the set of construction
392 elements that are supposed to be built. The building model coordinate sys-
393 tem needs to be transformed into the camera coordinate system or vice versa
394 in order to align both models. By applying this method, rendered images
395 from all points of acquisition are generated that allow the determination of
396 which elements are actually visible and can potentially be found in a gener-

397 ated point cloud. The resulting set of visible elements $E_V(t)$ enables greater
 398 detection accuracy.

399 The general approach for this method is explained in Braun and Bor-
 400 rmann [35], though for a slightly different application scenario. For further
 401 clarification, the key steps are explained in this section.

402 In order to calculate the projection, the intrinsic camera matrix for the
 403 distorted images that projects 3D points in the camera coordinate frame to
 404 2D pixel coordinates using the focal lengths (F_x, F_y) and the principal point
 405 (x_0, y_0) is required. Additionally, the skew coefficient s_k for the camera is
 406 required. It is zero if the image axes are perpendicular. The matrix K can
 407 be described as defined in equation 6.

$$K = \begin{bmatrix} F_x & s_k & x_0 \\ 0 & F_y & y_0 \\ 0 & 0 & 1 \end{bmatrix} \quad (6)$$

408 The translation of the camera is defined as:

$$T = \begin{bmatrix} t_1 \\ t_2 \\ t_3 \end{bmatrix} \quad (7)$$

409 Additionally, the rotation matrix for each image, as defined in equation
 410 8 is needed.

$$R = \begin{bmatrix} r_{11} & r_{12} & r_{13} \\ r_{21} & r_{22} & r_{23} \\ r_{31} & r_{32} & r_{33} \end{bmatrix} \quad (8)$$

411 Both, translation and rotation can be described in one 3 x 4 matrix:

$$RT = \begin{bmatrix} r_{11} & r_{12} & r_{13} & T_1 \\ r_{21} & r_{22} & r_{23} & T_2 \\ r_{31} & r_{32} & r_{33} & T_3 \end{bmatrix} \quad (9)$$

412 Using the model coordinates of all triangulated construction elements,
413 it is possible to calculate the projection of each element into the camera
414 coordinate system and therefore overlay the model projection and the corre-
415 sponding image taken from the point of observation with equation 10.

$$t = K * RT * p; \quad (10)$$

The resulting 2D coordinates that are rendered into the image are calculated by using the vector t and calculating the x and y coordinates by

$$x = t[0]/t[2] \quad (11)$$

and

$$y = t[1]/t[2] \quad (12)$$

416 With this projection, the model can be rendered from the camera's per-
417 spective for all images acquired during observation. After including the 4D
418 temporal information from the as-planned model, this information can be
419 fused, to render the model with the expected set of elements $E_P(t)$ from all
420 estimated camera positions. The term "rendering" here refers to the cre-
421 ation of the 2D projection of the model according to the rendering pipeline
422 established in computer graphics [43], but without applying advanced fea-
423 tures such as reflections, light sources or shading. These rendered images are

424 analyzed for all visible elements $E_V(t)$ by applying the Painter’s algorithm
425 [44]. With knowledge of this set of elements, the set $E_D(t)$ can be checked
426 for false positives, but also measured for accuracy regarding its true positive
427 rate. This is done by excluding elements from set $E_P(t)$ or $E_{GT}(t)$ that are
428 invisible from any camera position during acquisition.

429 *3.9. Image-based object detection*

430 To further enhance the detection of construction elements, we propose
431 making use of the images taken in the course of the initial acquisition for
432 the photogrammetric point cloud generation. By applying the previously
433 described projection technique, all construction elements can be localized on
434 any image taken during the acquisition. A sample is shown in Fig. 4: A col-
435 umn of interest is selected in the 3D view (marked red); detailed information
436 about this element is shown in the lower right. Accordingly, a corresponding
437 image that validated the existence of the selected element - and additionally
438 the 3D to 2D projection described in Section 3.8 - is used to display the
439 expected position of the element in this image.

440 As machine-learning methods have made significant advancements in re-
441 cent years, tasks like image classification or even region detection on images
442 are now being used in various scenarios. For the task of progress monitor-
443 ing, the authors propose the use of a Convolutional Neural Network (CNN)
444 trained on construction elements and thus able to detect the type and in-
445 stances of construction elements on the given images. In the case that an
446 element is not detected and validated by the point cloud, the implemented
447 workflow is followed as described in Fig. 5.

448 If the element is expected according to the up-to-date schedule and re-




Figure 4: Projection of a selected 3D geometry into the 2D plane of a corresponding image

449quires in-situ work, in a first step, the thresholds are increased as defined in
 450Sec. 3.6. If this helps to validate the elements' existence, it is added to the
 451set of detected elements $E_D(t)$. If not, the 2D projection, as mentioned in
 452Sec. 3.8, is used to identify the region of interest in a suitable image.

453Subsequently, the trained CNN [45] classifies the region according to the
 454predefined states and thus contributes to a refined state detection. If, e.g.,
 455formwork is detected here, the element can be marked as "under construc-
 456tion".

457In order to use a CNN for object-based region detection, the training of
 458said network is required. For this purpose, 5,000 images were labeled with
 459the categories *formwork*, *scaffolding*, *columns*, and *walls*. This resulted in
 4609,700 labeled formwork elements. The labeling procedure is depicted in Fig.
 4616. The data is converted into the COCO data format [46] and prepared for




Figure 5: Occluded construction elements in generated point cloud caused by scaffolding, formworks, existing elements and missing information during the reconstruction process

462 training by augmenting the images to enlarge the training set even further.



Figure 6: Sample image of the labeling process. Displayed are the labeled formwork (blue) and column (green) elements. During this research, Labelbox [47] is used for labeling.

463 To sum up, all introduced methods make the overall process much more
464 robust compared to a purely geometry-based approach, and lead to a higher
465 detection accuracy.

466 4. Case Study

467 Several construction sites were monitored with different observation meth-
468 ods to validate the introduced concepts. The construction sites are all
469 German-based and cover a number of structural engineering buildings as well
470 as infrastructure (one bridge, one wastewater treatment plant). The main

471 construction method is in-situ concreting, this being the most common con-
 472 struction technique in Germany. Listed in Table 1 are the three construction
 473 sites that are used as case studies in this section.

Site	Elements	Observations	Pictures taken	Duration
Test Site A	671	6	1,805	5 months
Test Site B	943	9	2,350	10 months
Test Site C	2,229	23	3,144	5 months

Table 1: Test sites monitored during this case study

474 In this context, the authors published several papers presenting their ap-
 475 proach and developed a software framework, which was introduced in Braun
 476 et al. [29] and shown in Figure 7. To visualize the comparison results and
 477 the detected elements, and to verify the used algorithms, all gathered data is
 478 stored in a database that is accessible via this software. The tool displays all
 479 geometric and semantic building element information as well as scheduling
 480 data that has been parsed from IFC instance models. The detected elements
 481 are highlighted for easy identification. Figure 7 shows the software interface
 482 with the example of one of the construction-site case studies used in this
 483 research. The building mainly consists of in-situ concrete elements that were
 484 cast using formwork on site. In the figure, one individual capturing event
 485 is selected, and all detected elements are highlighted. Green coloring repre-
 486 sents elements that have been built and are correctly detected and confirmed
 487 through the point cloud. All yellow elements are built but were not confirmed
 488 through the point cloud.

489 There are several reasons why some of those elements may not be de-




Figure 7: Screenshot of a developed tool for as-planned vs. as-built comparison. A specific observation is selected to visualize the detected construction elements at that time. Details of selected elements are shown in a separate viewer.

490 tected. The most prominent reason is the occlusions that occur on site. Dur-
491 ing construction, large amounts of temporary structures like scaffolds, con-
492 struction tools, and construction machinery obstruct the view of the element
493 surfaces. Limited acquisition positions further reduce the visible surfaces
494 and hence the overall quality of the generated point clouds. Additionally,
495 elements inside of the building are also occluded by other building elements
496 for acquisitions outside of the building.

497 Another reason for weak detection rates is building elements that are
498 currently under construction. As those elements count towards the overall
499 progress, they must not be missed, and play a crucial role in defining the
500 exact state in the current process. In general challenges exist for all con-
501 struction methods, whose geometry under construction differs largely from
502 the final element geometry which requires the use of temporary construction
503 objects. This applies, e.g., to reinforced concrete and multi-layered walls.
504 On the one hand, formwork which is used for concrete pouring, may ob-
505 struct the view of the element, making it impossible to be detected. On the
506 other hand, the plane surface of formwork for a slab might be detected as
507 the surface of the slab itself and thus would lead to a false positive. Due
508 to these challenges, further enhancements to the comparison and detection
509 algorithms are needed. Since the digital model contains information on con-
510 struction methods, the authors propose using this knowledge in the overall
511 detection process. By deducing the precedence relationships with a query
512 language, assumptions regarding occluded elements can be made. Construc-
513 tion methods and derivation of expected elements lead to new as-planned
514 vs. as-built comparison capabilities, such as extended thresholds and com-

515 puter vision methods to detect objects like formwork on the raw observation
516 images, taken for the point cloud generation.

517 *4.1. Precedence Relationship Graph*

518 The PRG for all construction sites is generated by using a query language
519 for Building Information Models (QL4BIM, Daum and Borrmann [40]). With
520 the algorithm introduced in Sec. 3.5, any building information model that
521 has sufficient semantic information can be analyzed, and technological de-
522 pendencies are formalized by the introduced graph. Fig. 8 shows the PRG
523 for one of the mentioned case studies. Each node represents one construction
524 element; the directed edges show the corresponding dependency.

525 Based on the detected elements (marked in green and yellow), all depen-
526 dent elements can be identified via this graph. Specifically, this graphs allows
527 one to make assumptions regarding the construction elements that were ei-
528 ther invisible during observation, or were not detected due to occlusions or
529 other issues (as mentioned before). The elements marked in blue in Fig. 8
530 are identified as depending elements with this method.

531 Table 2 shows detailed enhancements for the introduced PRG. In particu-
532 lar, a significant amount of construction elements were identified as depend-
533 ing upon the detected elements. In this respect, these elements are logically
534 required to be built despite the fact that they were not confirmed visually
535 by the point cloud.

536 This information helps to obtain additional information for the as-planned
537 vs. as-built comparison: if a slab is built, all load-bearing elements under-
538 neath it must have been built, even though they cannot be verified by any
539 visual method.




Figure 8: Generated precedence relationship graph for Test Site A. Elements marked blue were derived from the PRG in combination with the detected elements marked in green and yellow.

Date	$E_{GT}(t)$	$E_D(t)$	$\delta E_{PRG}(t)$
15.05.	89	37	20
12.06.	152	32	57
27.06.	184	59	54
17.07.	233	53	85
06.08.	277	95	102
04.09.	342	98	159

Table 2: Enhancing results by applying the introduced PRG for Case Study site A

540 *4.2. Varying dimensions*

541 Figure 9 depicts a part of a snippet of a point cloud, generated at one
542 individual time-step during observation. It is overlaid with the corresponding
543 3D geometry and visualized in green, to symbolize the as-planned as well as
544 the as-built status. Based on this example, the general workflow for elements
545 under construction is shown. As depicted, the front wall is already finished,
546 and the concrete surface is visible. The wall in the second row is currently
547 under construction, and the formwork is present and registered in the point
548 cloud.




Figure 9: Point cloud of a finished, plain wall and formwork overlaid with the corresponding 3D geometry on Test Site B

549 During detection, it is expected that the first row of walls will be detected.
550 Due to the threshold of max. 1 cm, the second row should not be detected due

551 to the formwork. Figure 10 a) shows the expected result, with an additional
 552 set threshold of $1000 \text{ points}/\text{m}^2$ (in green). Triangles marked in yellow have
 553 matching points but do not qualify for the set thresholds, while elements
 554 marked red have no qualifying points at all. The walls in the second row
 555 are expected to be in progress. As presented in the concept in Section 3,
 556 the detection is therefore carried out with a larger threshold. Based on this
 557 result, the accepted point-to-surface distance is increased to 10 cm, which
 558 leads to the results depicted in Figure 10 b).




Figure 10: Triangles detected during the time-step shown in Figure 9. a) with 1cm gaps and $\rho > 1000\text{pts}/\text{m}^2$, b) with 10cm gaps and $\rho > 1000\text{pts}/\text{m}^2$

559 The increased threshold leads to the expected higher point density on the
 560 wall under construction, as the formwork is considered, too. According to
 561 the introduced workflow, the wall is now marked as "under construction",
 562 leading to a further detailed automated progress monitoring.

563 4.3. Color detection for formwork and reinforcement

564 As detailed in Section 3, taking colors into account can improve the detec-
 565 tion of formwork or reinforcements due to their significantly varying colors,
 566 in comparison to the grey colors of the concrete. The color values of the
 567 different elements were compared to prove this statement. Figure 11 shows




Figure 11: Distribution of frequency in the HSV color space shows clear deviations between concrete and formwork elements with the Hue value represented by blue bars and Saturation value represented by orange bars.

568 the calculated mean values for different elements under different lighting con-
 569 ditions.

570 In calculating the mean HSV values, all points relevant to an element are
 571 considered, along with the relevant color information. The results show that
 572 the brightness (value) varies largely, which is due to the lighting conditions
 573 itself. Therefore, this value has no further significance for this study. How-
 574 ever, the hue values for formwork fall into the correct range for warm, red
 575 colors, whereas the concrete walls are based on "colder" colors. Additionally,
 576 the saturation differs by at least a factor 2.3. This color distribution analysis
 577 at a point-cloud level allows automated color interpretation to be carried out,
 578 and helps to identify differences between expected and actual color ranges
 579 based on material properties. The described process is used during the whole
 580 comparison to obtain a higher accuracy of information.

581 4.4. *Visible elements*

582 The visibility analysis is tested on several construction sites. Fig. 12
583 shows four samples from different observation times and construction sites.
584 Each element has a unique color for identification purposes.




Figure 12: Visibility analysis with rendered geometry of set $E_P(t)$ for several construction sites and observations. All elements are rendered in different colors to distinguish them from each other.

585 Based on these results, all visible elements are identified and added to a
586 corresponding set $E_V(t)$. This additional step does not detect any additional
587 elements during the as-planned vs. as-built process, however it helps to set
588 the detection results in a more accurate context. In detail, false positives

589 can be reduced by removing invisible elements. Additionally, the thresholds
 590 used for the comparison process can be validated in a more precise manner,
 591 as the invisible elements are not added to the set of not detected elements.

592 Table 3 shows this data for one of our case studies during the whole
 593 observation period.

Date	$E_{GT}(t)$	$E_D(t)$	$E_V(t)$	$\%_{Vis}$
15.05.	89	37	73	82.0 %
12.06.	152	32	122	80.3 %
27.06.	184	59	155	84.2 %
17.07.	233	53	214	91.8 %
06.08.	277	95	275	99.3 %
04.09.	342	98	325	95.0 %

Table 3: Visible elements based on the introduced algorithm for Test Site A.

594 4.5. Image-based object detection

595 For the image-based object detection described in Sec. 3.9 we trained a
 596 Mask R-CNN-based [45] neural network using a training set consisting of over
 597 5,000 images from five different construction sites and 40 observations with
 598 9,700 labeled formwork elements and around 5,000 labeled column elements.
 599 Depicted in Figure 14, the results for formwork and column elements are
 600 shown in an image that was not part of the training set. A common method
 601 to quantify the estimated result is the mean average precision that calculates
 602 as

$$Precision = \frac{TruePositives}{TruePositives + FalsePositives} \quad (13)$$

603 In combination with the recall

$$Recall = \frac{TruePositives}{TruePositives + FalseNegatives} \quad (14)$$

604 the harmonized F_1 score can be calculated as:

$$F_1score = 2 * \frac{Precision * Recall}{Precision + Recall} \quad (15)$$

605 An ideal network with perfect precision and recall values would achieve
 606 a F_1 score of 1. The trained network has a mean average precision (mAP)
 607 of 90.7% with an IoU (Intersection over Union) of 0.5 over all categories.
 608 With $TP = 11731$, $FP = 1099$ and $FN = 928$, the precision is at 0.914,
 609 the recall at 0.927, resulting in an $F_1Score = 0.920$ proving the suitability of
 610 the implemented methods. Fig. 13 shows the corresponding precision-recall
 611 curve for the trained network.

612 It has been tested against previously unknown images from the internet
 613 and other construction sites.

614 The results of this image-based region detection are subsequently used
 615 for the as-planned vs. as-built comparison. As introduced in Figure 5, con-
 616 struction elements that have not been verified by the point cloud, are run
 617 through an additional workflow, in order to check for formwork elements.
 618 If the CNN verifies the existence of a formwork element, the corresponding
 619 concrete structure is labeled as "under construction", making the process
 620 estimation more accurate. After testing this approach on a real-world con-
 621 struction site, this additional step proved to be suitable for construction sites




Figure 13: Precision-recall Curve for the trained network



Figure 14: Formwork and column elements detected by a trained CNN using Mask R-CNN on Test Site C

622 that use in-situ concreting as a manufacturing method. Table 4 shows the
 623 amount of detected formwork elements with the help of the trained network.

Date	15.05.	12.06.	27.06.	17.07.	06.08.	04.09.
Detected	9	11	8	2	0	8

Table 4: Detected formwork elements during the observations for Test Site A.

624 4.6. Results

625 After the evaluation of all steps, the methods are incorporated into the
 626 presented software framework. Table 5 shows the results for one of our case
 627 studies during the complete construction process. During the initial, point-
 628 cloud-based comparison, the following data was gathered:

Date	$E_P(t)$	$E_{GT}(t)$	$E_D(t)$	$E_{FP}(t)$	$A_D(t)[m^2]$	$A_{GT}(t)[m^2]$	$\%_A$
15.05.	60	89	37	2	1,162.76	1916.95	60.66 %
12.06.	133	152	32	11	1,326.95	3,557.74	37.3 %
27.06.	240	184	59	0	2,244.51	4,808.6	46.68 %
17.07.	348	233	53	5	4,147.65	6,261.07	66.25 %
06.08.	456	277	95	1	4,480.78	6,773.9	66.15 %
04.09.	569	342	98	1	4,763.63	9,197.7	51.79 %

Table 5: Resulting element sets for Test Site A

629 According to this data, the detection rates differ over a range of 37 % to
 630 66 % correctly detected elements, based on the area surfaces. As mentioned
 631 above, these results largely depend on the point-cloud density and recon-

632 construction quality from the SfM process. For any construction planner, these
 633 results would be insufficient as a comprehensive progress-monitoring tool.

634 After applying the newly introduced methods to this initial as-planned
 635 vs. as-built comparison, these additional results were gathered as shown in
 636 Table 6 with detected, cast elements defined as $E_{FW}(t)$ and elements inferred
 637 by the PRG, in addition to the previously detected elements, as $\delta E_{PRG}(t)$.

638 This table summarizes the results of the previous sections.

Date	$E_V(t)$	$E_{FW}(t)$	$\delta E_{PRG}(t)$	$E_{D_{new}}(t)$	$A_D(t)[m^2]$	$A_V(t)[m^2]$	$\%_A$
15.05.	73	9	20	66	1509.42	1681.04	83.8 %
12.06.	122	11	57	100	2792.95	3284.76	85.0 %
27.06.	155	8	54	121	3975.51	4579.60	86.8 %
17.07.	214	2	85	140	4975.65	6059.13	82.1 %
06.08.	275	0	102	197	5780.78	6644.94	87.0 %
04.09.	325	8	159	265	7675.58	9021.86	85.1 %

Table 6: Enhanced results for the detection with the newly introduced methods for Test Site A.

639 As shown, the number of detected true positives is raised significantly by
 640 applying the introduced steps. The newly detected rates all lie in the range
 641 between 80% to 90% of the actually built elements. An improvement of
 642 more than 100% in detected elements in comparison to the pure point-cloud
 643 vs. geometry-based detection methods was achieved. To draw conclusions
 644 from the results, there is still potential for further improvements. However,
 645 the introduced methods were tested on real-world construction sites over the
 646 complete construction cycle, and not only on a limited test area which usually

647 constitutes a more controlled environment. Real-world data from construc-
648 tion sites always introduces many occlusions, and non-modeled elements that
649 make it nearly impossible to detect all elements on a construction site.

650 **5. Discussion and Outlook**

651 *5.1. Conclusion*

652 Detailed progress monitoring is of utmost importance for efficient con-
653 struction site management as it allows delays to be identified early, and for
654 respective counter-measures to be taken. Matching the as-designed 4D build-
655 ing information model to point clouds provides a suitable basis for automat-
656 ing this process. The general approach of Scan-vs-BIM has been proposed
657 and investigated by a number of researchers in recent years. In this paper, a
658 number of methods are introduced that further improve the accuracy of the
659 detection process of the as-planned vs. as-built comparisons. The common
660 approach lies in fusing information generated by different techniques and
661 from different sources, namely the images, the point cloud and the building
662 information model. The formal description of the technological dependencies
663 in the construction process in the form of a precedence relationship graph al-
664 lows the inference of status information on components that are not directly
665 detectable. Image-based color detection and a higher threshold for elements
666 with possible formwork in place enable the correct identification of elements
667 that are under construction at the time of capturing the site. As a core
668 contribution, the paper presents how CNN-based object-detection methods
669 are applied to the captured images to correctly detect elements that tend to
670 be otherwise falsely classified. Significant synergies are created by training

671 the network with images that are automatically labeled, by applying Scan-
672 vs-BIM techniques. The use of image-based object detection extends the
673 reliability of the status-detection process significantly, due to the larger den-
674 sity of pixel-based information, in comparison with a pure point-cloud-based
675 approach.

676 *5.2. Limitations*

677 It is crucial to note that the image data can only be used thanks to the
678 photogrammetric process and the underlying camera pose estimation. Laser
679 scanners usually do not provide this data and are therefore not suitable for
680 this approach. Another limitation is the requirement for a well-aligned BIM.
681 In our approach, this is achieved by markers on site. However, a minor
682 manual step is required in order to find the exact orientation and scaling.
683 Only after combining this data with the aligned building information model
684 is it possible to gather additional information from the images in relation to
685 the building model.

686 The described ML approach is limited to the provided training data. This
687 data currently only includes construction sites in Germany, which might make
688 the network biased and unsuitable for different regions that use different
689 construction methods. The observed construction sites so far mainly used
690 in-situ concreting and a small number of prefabricated elements.

691 *5.3. Outlook*

692 All introduced methods enhance the automated construction progress
693 monitoring workflow. However, it is still the case that not all elements can

694 be detected. Better acquisition methods will play an essential role in solv-
695 ing these issues. Several research groups have proposed different acquisition
696 methods to detect indoor elements, too. A combination of all these methods
697 could help to improve element detection even further.

698 More comprehensive data sets for image-based ML are required to cover
699 different construction methods and materials from other regions.

700 **Acknowledgments**

701 We would like to thank the Leibniz Supercomputing Centre (LRZ) of the
702 Bavarian Academy of Sciences and Humanities (BAdW) for the support and
703 provision of computing infrastructure essential to this publication. We would
704 like to thank the German Research Foundation (DFG) for funding the initial
705 project of progress monitoring.

706 Additionally, we would like to thank our students Bernhard Mueller
707 and Sebastian Behnke for their support during the labeling and machine-
708 learning training phase. The support of all construction companies, pro-
709 viding data for the research conducted in this field is much appreciated:
710 Adidas, Leitner GmbH & Co Bauunternehmung KG, Kuehn Malvezzi Ar-
711 chitects, Staatliches Bauamt Muenchen, Baugesellschaft Brunner+Co, BKL
712 Baukranlogistik GmbH, Geiger Gruppe, Baureferat H5, Landeshauptstadt
713 Muenchen, Baugesellschaft Mickan mbH & Co KG, h4a Architekten, Wenzel
714 + Wenzel, Zueblin, and Stadtvermessungsamt Muenchen.

715 **References**

- 716 [1] B. Hardin, D. McCool, BIM and construction management : proven
717 tools, methods, and workflows, Wiley, ISBN: . 9781118942765.
- 718 [2] F. Bosché, C. Haas, Automated retrieval of 3D CAD model objects
719 in construction range images, *Automation in Construction* 17 (2008)
720 499–512. doi:10.1016/j.autcon.2007.09.001.
- 721 [3] M. Golparvar-fard, F. Pena-Mora, S. Savarese, D4AR - a 4 dimen-
722 sional augmented reality model for automation construction progress
723 monitoring data collection, processing and communication, *Jour-
724 nal of Information Technology in Construction* 14 (2009) 129–153.
725 doi:<https://www.itcon.org/paper/2009/13>.
- 726 [4] J. J. Lin, K. K. Han, M. Golparvar-Fard, A Framework for
727 Model-Driven Acquisition and Analytics of Visual Data Us-
728 ing UAVs for Automated Construction Progress Monitoring,
729 in: *Computing in Civil Engineering 2015*, American Soci-
730 ety of Civil Engineers, Reston, VA, 2015, pp. 156–164. URL:
731 <http://ascelibrary.org/doi/10.1061/9780784479247.020>.
732 doi:10.1061/9780784479247.020.
- 733 [5] C. Wu, Towards linear-time incremental structure from
734 motion, in: *Proceedings - 2013 International Conference
735 on 3D Vision, 3DV 2013*, IEEE, 2013, pp. 127–134. URL:
736 <http://ieeexplore.ieee.org/articleDetails.jsp?arnumber=6599068>.
737 doi:10.1109/3DV.2013.25.

- 738 [6] A. Braun, S. Tuttas, U. Stilla, A. Borrmann, Incorporating knowl-
739 edge on construction methods into automated progress monitoring tech-
740 niques, in: 23rd International Workshop of the European Group for In-
741 telligent Computing in Engineering, EG-ICE 2016, 2016, pp. 1–11. URL:
742 <https://publications.cms.bgu.tum.de/2016BraunEGICE.pdf>.
- 743 [7] W. Huhnt, S. Richter, F. Enge, Modification Management for Construc-
744 tion Processes, *Tsinghua Science and Technology* 13 (2008) 185–191.
745 doi:10.1016/S1007-0214(08)70147-0.
- 746 [8] J. Tulke, Kollaborative Terminplanung auf Basis von Bauwerksinforma-
747 tionsmodellen, Ph.D. thesis, Bauhaus Universität Weimar, 2010. URL:
748 <https://d-nb.info/1116284456/34>.
- 749 [9] C. Kropp, C. Koch, M. König, Drywall State Detection in Im-
750 age Data for Automatic Indoor Progress Monitoring, in: *Com-
751 puting in Civil and Building Engineering (2014)*, American So-
752 ciety of Civil Engineers, Reston, VA, 2014, pp. 347–354. URL:
753 <http://ascelibrary.org/doi/10.1061/9780784413616.044>.
754 doi:10.1061/9780784413616.044.
- 755 [10] T. Omar, M. L. Nehdi, Data acquisition technologies for construc-
756 tion progress tracking, *Automation in Construction* 70 (2016) 143–155.
757 doi:10.1016/j.autcon.2016.06.016.
- 758 [11] Z. Pučko, N. Šuman, D. Rebolj, Automated continuous con-
759 struction progress monitoring using multiple workplace real time

- 760 3D scans, *Advanced Engineering Informatics* 38 (2018) 27–40.
761 doi:10.1016/j.aei.2018.06.001.
- 762 [12] F. Bosché, Plane-based registration of construction laser scans with
763 3D/4D building models, *Advanced Engineering Informatics* 26 (2012)
764 90–102. doi:10.1016/j.aei.2011.08.009.
- 765 [13] F. Bosché, Automated recognition of 3D CAD model objects in laser
766 scans and calculation of as-built dimensions for dimensional compliance
767 control in construction, *Advanced Engineering Informatics* 24 (2010)
768 107–118. doi:10.1016/j.aei.2009.08.006.
- 769 [14] Y. Turkan, F. Bosché, C. T. Haas, R. Haas, Automated progress track-
770 ing using 4D schedule and 3D sensing technologies, *Automation in Con-
771 struction* 22 (2012) 414–421. doi:10.1016/j.autcon.2011.10.003.
- 772 [15] C. Kim, B. Kim, H. Kim, 4D CAD model updating using image
773 processing-based construction progress monitoring, *Automation in Con-
774 struction* 35 (2013) 44–52. doi:10.1016/j.autcon.2013.03.005.
- 775 [16] M. Golparvar-Fard, F. Peña-Mora, S. Savarese, Automated Progress
776 Monitoring Using Unordered Daily Construction Photographs and
777 IFC-Based Building Information Models, *Journal of Computing in
778 Civil Engineering* 29 (2015) 04014025. doi:10.1061/(ASCE)CP.1943-
779 5487.0000205.
- 780 [17] S. Tuttas, A. Braun, A. Borrmann, U. Stilla, Validation of Bim Com-
781 ponents By Photogrammetric Point Clouds for Construction Site Moni-
782 toring, *ISPRS Annals of Photogrammetry, Remote Sensing and Spatial*

- 783 Information Sciences II-3/W4 (2015) 231–237. doi:10.5194/isprsannals-
784 II-3-W4-231-2015.
- 785 [18] C. C. Kim, H. Son, C. C. Kim, Fully automated registration of 3D data
786 to a 3D CAD model for project progress monitoring, *Automation in*
787 *Construction* 35 (2013) 587–594. doi:10.1016/j.autcon.2013.01.005.
- 788 [19] C. Zhang, D. Arditì, Automated progress control using laser scan-
789 ning technology, *Automation in Construction* 36 (2013) 108–116.
790 doi:10.1016/j.autcon.2013.08.012.
- 791 [20] H. Mahami, F. Nasirzadeh, A. Hosseininaveh Ahmadabadian, S. Na-
792 havandi, Automated Progress Controlling and Monitoring Using Daily
793 Site Images and Building Information Modelling, *Buildings* 9 (2019) 70.
794 doi:10.3390/buildings9030070.
- 795 [21] Y. Ibrahim, T. Lukins, X. Zhang, E. Trucco, a. Kaka, Towards auto-
796 mated progress assessment of workpackage components in construction
797 projects using computer vision, *Advanced Engineering Informatics* 23
798 (2009) 93–103. doi:10.1016/j.aei.2008.07.002.
- 799 [22] K. Asadi, H. Ramshankar, M. Noghabaei, K. Han, Real-Time Image Lo-
800 calization and Registration with BIM Using Perspective Alignment for
801 Indoor Monitoring of Construction, *Journal of Computing in Civil Engi-
802 neering* 33 (2019) 04019031. doi:10.1061/(ASCE)CP.1943-5487.0000847.
- 803 [23] C. Kropp, C. Koch, M. König, Interior construction state recognition
804 with 4D BIM registered image sequences, *Automation in Construction*
805 86 (2018) 11–32. doi:10.1016/j.autcon.2017.10.027.

- 806 [24] Y. Turkan, F. Bosché, C. T. Haas, R. Haas, Tracking of secondary and
807 temporary objects in structural concrete work, *Construction Innovation*
808 14 (2014) 145–167. doi:10.1108/CI-12-2012-0063.
- 809 [25] K. K. Han, M. Golparvar-Fard, Appearance-based material classifica-
810 tion for monitoring of operation-level construction progress using 4D
811 BIM and site photologs, *Automation in Construction* 53 (2015) 44–57.
812 doi:10.1016/j.autcon.2015.02.007.
- 813 [26] K. K. Han, D. Cline, M. Golparvar-Fard, Formalized knowledge of
814 construction sequencing for visual monitoring of work-in-progress via
815 incomplete point clouds and low-LoD 4D BIMs, *Advanced Engineering*
816 *Informatics* 29 (2015) 889–901. doi:10.1016/j.aei.2015.10.006.
- 817 [27] I. C. Wu, A. Borrmann, U. Beißert, M. König, E. Rank, Bridge con-
818 struction schedule generation with pattern-based construction methods
819 and constraint-based simulation, *Advanced Engineering Informatics* 24
820 (2010) 379–388. doi:10.1016/j.aei.2010.07.002.
- 821 [28] K. Szczesny, M. Hamm, M. König, Adjusted recombination operator for
822 simulation-based construction schedule optimization, in: *Proceedings*
823 *of the 2012 Winter Simulation Conference, 2012*, pp. 1219–1229. URL:
824 <https://dl.acm.org/citation.cfm?id=2429835>.
- 825 [29] A. Braun, S. Tuttas, A. Borrmann, U. Stilla, Automated Progress Mon-
826 itoring Based on Photogrammetric Point Clouds and Precedence Rela-
827 tionship Graphs, in: *Proceedings of the 32nd International Symposium*

- 828 on Automation and Robotics in Construction and Mining (ISARC 2015),
829 2017, pp. 274–280. doi:10.22260/isarc2015/0034.
- 830 [30] H. Hamledari, B. McCabe, S. Davari, A. Shahi, Automated Schedule
831 and Progress Updating of IFC-Based 4D BIMs, *Journal of Computing*
832 *in Civil Engineering* 31 (2017) 04017012. doi:10.1061/(ASCE)CP.1943-
833 5487.0000660.
- 834 [31] Y. LeCun, Y. Bengio, G. Hinton, Deep learning, *Nature* 521 (2015)
835 436–444. doi:10.1038/nature14539.
- 836 [32] B. Akinici, F. Boukamp, C. Gordon, D. Huber, C. Lyons, K. Park, A
837 formalism for utilization of sensor systems and integrated project models
838 for active construction quality control, *Automation in Construction* 15
839 (2006) 124–138. doi:10.1016/j.autcon.2005.01.008.
- 840 [33] H. Nhat-Duc, Q. L. Nguyen, V. D. Tran, Automatic recognition of
841 asphalt pavement cracks using metaheuristic optimized edge detection
842 algorithms and convolution neural network, *Automation in Construction*
843 94 (2018) 203–213. doi:10.1016/j.autcon.2018.07.008.
- 844 [34] K. Han, M. Golparvar-Fard, Crowdsourcing BIM-guided collection of
845 construction material library from site photologs, *Visualization in En-*
846 *gineering* 5 (2017) 14. doi:10.1186/s40327-017-0052-3.
- 847 [35] A. Braun, A. Borrmann, Combining inverse photogrammetry and
848 BIM for automated labeling of construction site images for ma-
849 chine learning, *Automation in Construction* 106 (2019) 102879.
850 doi:10.1016/j.autcon.2019.102879.

- 851 [36] S. Chi, C. H. Caldas, Automated Object Identification Using Op-
852 tical Video Cameras on Construction Sites, *Computer-Aided Civil*
853 *and Infrastructure Engineering* 26 (2011) 368–380. doi:10.1111/j.1467-
854 8667.2010.00690.x.
- 855 [37] H. Hamledari, B. McCabe, S. Davari, Automated computer
856 vision-based detection of components of under-construction in-
857 door partitions, *Automation in Construction* 74 (2017) 78–94.
858 doi:10.1016/j.autcon.2016.11.009.
- 859 [38] S. Tuttas, A. Braun, A. Borrmann, U. Stilla, Acquisition and Consec-
860 utive Registration of Photogrammetric Point Clouds for Construction
861 Progress Monitoring Using a 4D BIM, *Photogrammetrie, Fernerkun-*
862 *dung, Geoinformation* 85 (2017). doi:10.1007/s41064-016-0002-z.
- 863 [39] G. W. Zobrist, J. V. Leonard, *Progress in simulation*, Intellect Books,
864 1992. ISBN: , 978-0893916527.
- 865 [40] S. Daum, A. Borrmann, Processing of Topological BIM Queries us-
866 ing Boundary Representation Based Methods, *Advanced Engineering*
867 *Informatics* 28 (2014) 272–286. doi:10.1016/j.aei.2014.06.001.
- 868 [41] S. Tuttas, A. Braun, A. Borrmann, U. Stilla, Evaluation of acquisition
869 strategies for image-based construction site monitoring, in: *Interna-*
870 *tional Archives of the Photogrammetry, Remote Sensing and Spatial*
871 *Information Sciences - ISPRS Archives*, volume 41, ISPRS Congress,
872 Prague, Czech Republic, 2016, pp. 733–740. doi:10.5194/isprsarchives-
873 XLI-B5-733-2016.

- 874 [42] S. Sural, Gang Qian, S. Pramanik, Segmentation and histogram gener-
875 ation using the HSV color space for image retrieval, in: Proceedings.
876 International Conference on Image Processing, volume 2, IEEE, 2003,
877 pp. II-589-II-592. doi:10.1109/icip.2002.1040019.
- 878 [43] J. D. Foley, J. D. Foley, Computer graphics : principles and practice,
879 Addison-Wesley, ISBN: . 0201121107.
- 880 [44] T. T. Elvins, A survey of algorithms for volume visualiza-
881 tion, ACM SIGGRAPH Computer Graphics 26 (2005) 194-201.
882 doi:10.1145/142413.142427.
- 883 [45] K. He, X. Zhang, S. Ren, J. Sun, Deep Residual Learning
884 for Image Recognition, in: 2016 IEEE Conference on Com-
885 puter Vision and Pattern Recognition (CVPR), IEEE, 2016, pp.
886 770-778. URL: <http://ieeexplore.ieee.org/document/7780459/>.
887 doi:10.1109/CVPR.2016.90.
- 888 [46] M. Andriluka, L. Pishchulin, P. Gehler, B. Schiele, 2D Human Pose
889 Estimation: New Benchmark and State of the Art Analysis, in:
890 2014 IEEE Conference on Computer Vision and Pattern Recognition,
891 IEEE, 2014, pp. 3686-3693. URL: <http://arxiv.org/abs/1405.0312>
892 <http://ieeexplore.ieee.org/lpdocs/epic03/wrapper.htm?arnumber=6909866>.
893 doi:10.1109/CVPR.2014.471.
- 894 [47] Labelbox, training data workbench, 2020. URL: www.labelbox.com, ac-
895 cessed: 2020-01-15.